



HolzKnecht Enterprises LLC

P.O. BOX 536


Plainfield, IN 46168

Estimate

Date	Estimate #
5/12/2025	

Name / Address
Town of Avon 6570 E. US 36 Avon, IN 46123

Project

Description	Qty	Cost	Total
INSTALL 55 FT OF 24" POLYPROPYLENE PIPE ACROSS CR 100 N JUST WEST OF RONALD REAGAN...CUT ASPHALT AND REMOVE EXISTING PIPE, INSTALL 27.5 FT OF PIPE, BACK FILL PIPE WITH FLOWABLE FILL AND TOP WITH ASPHALT WHILE KEEPING THE OTHER HALF OF THE ROAD OPEN TO KEEP TRAFFIC MOVING. REPEAT PROCESS ON THE OTHER HALF OF THE ROAD ONCE THE REPAIRED SECTION IS OPENED. INSTALL RIP RAP ON END SECTIONS AND SEED AND STRAW BLANKET		27,798.00	27,798.00
<p>This quote for emergency repair is approved.</p>  Steve Moore, Public Works Director 5/14/2025			
		Total	\$27,798.00